

## **IMPORTANT NOTES:**

- 1. Insert the proper size support legs & solvent cement the Sleeve Coupling to the tub box socket.
- 2. Use nails through the leg & flange holes to mount box to deck.
- 3. After the concrete pour and before setting tub, remove styrofoam and knock out test cap. Use a 1-1/2" plastic or brass waste & overflow and drop through the Sleeve Coupling.
- 4. Install a P-25661 (pipe size) or P-25662 (tube size) ProSeal Plug to seal the bottom of sleeve.
- 5. Fill the void between the pass through pipe and the sleeve with Firefill material to a minimum depth of 4"- If the 4" fill can not be obtened inside the sleeve coupling, install the Firefill into the tub box itself.

Important: The above installation drawing is used when the concrete slab is less than 7".

When the concrete floor depth is 7" or more refer to Drawing No. C-6212-A for different installation instructions.



W.H. Directory Reference 99 Edition Firestop Device W.H. Design No. PS/PH 120-11 F Rating 2 Hrs.



DATE : 5-31-21

DRG . NO . C-6211-A